

SCHEDULE OF QUANTITIES

Subject : Renovation of Mess Civil Works, Mandi House

S. No.	Description	Unit	Rate (Rs.)	Quantity	Amount (Rs.)
1.	Centering & Stuttering including Strutting propping etc. for all heights	Sqft.		500	
2.	Brick work with bricks of class designation 75 in foundation & Plinth in: Cement mortar 1:4 (1 Cement :4 coarse sand) and super structure including dismantling existing B/W	Cuft		900	
3.	Bolts nd Anchors for the base plate and fixing of the truss and the lighting frame below up to 300mm length.	Kilogram		300	
4.	Structural Steel work riveted or bolted in built up sections, trusses & framed work including cutting hoisting & fixing in position & applying a priming coat of approved steel primer all complete including the base plates.	Kilogram		1350	
5.	Welding by plant including transportation of welding plant at site etc. complete	Cm length		3000	
6.	Providing asbestos cement 6mm thick corrugated sheets roofing & fixing with polymer coated J or L hooks bolts & nuts 8 mm. dia. GI plain & bitumen washers complete excluding the cost of prulins, rafters & trusses : corrugated sheets : Above 60 degrees pitch.	Sqft.		600	
7.	Providing & fixing ridges & hips in asbestos cement sheet roofing : one piece plain angular ridges.	Ft.		25	
8.	Providing & fixing asbestos cement roofing accessories with polymer coated J & L hooks bolts & nuts & or GI seam bolts & nuts,GI plain & bitumen washer complete for complete roof with joint fillings	Sqft.		300	
9.	Providing flat iron brackets 50x3 mm size with necessary bolts, nuts & washers etc. for fixing of asbestos cement /G.S. Sheets gutters with purlins	Ft.		60	
10.	12mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement : 4 Fine sand) including chipping of the existing plaster .	Sqft		1000	
11.	External Plaster 19mm thick	Sqft.		980	
12.	Water Proofing over the roof for the	Sqft.		600	

	removal of the water seepage with a warranty of 1 year in the form a certificate				
13.	Misc. repair jobs and other works required for the rectification during the construction	Sqft.		600	
14.	Shifting of the existing manhole to a new position as per the location with a	Lumpsum			
15.	P/F door window in aluminium with 6 mm glass complete with all accessories powder coated in white finish.	Sqft.		180	

Estimated value as per the market trends.

- Note :- (1) Work shall be done as per CPWD specifications.
(2) Malba to be removed from site and nothing shall be paid
(3) 5% Security Deposit shall be deducted from gross amount of bill and will be released six months from the date of completion .