

## SCHEDULE OF QUANTITIES

Name of Work :- Providing and fixing Gyp board ceiling in Gym, Video Library, Repair of Girl's Hostel entrance Lobby and Glass brick wall in front of Gent & Ladies Toilet near Mess.

Sl. No.	Description of items	Quantity	Unit	Rate	Amount
1.	<p>Providing &amp; Fixing false ceiling of Gyp. Board with approved pattern using I.S.I Standard materials T-Sections 35 x 15 x 1.5 mm size main runners and cross runners 23.5 x 19 x 1.5 mm fixed to main runners place 600 mm centre to centre both ways so as to form grid of 600 mm square. The frame work shall be suspended from ceiling by level adjusting hangers of 6 mm diameter M.S.Rod fixed to roof slab by means of ceiling cleats. The Suspenders shall be placed 600 x1200mm centre to centre with two coats of synthetic enamel paint of approved quality complete.</p> <p style="margin-left: 40px;">Gym - 459 sqft. Video Library - 425 sqft. ----- 884 sqft.</p>	884	Sqft.		
2.	<p>Dismantling false ceiling</p> <p style="margin-left: 40px;">Video Library - 425 sqft.</p>	425	Sqft.		
3.	<p>Repair of Mangalore tiles for arresting leakage with cement mortor mixed with water proofing cement compound</p> <p style="margin-left: 40px;">Gym - 660 sqft.</p>	660	Sqft.		

Sl. No.	Description of items	Quantity	Unit	Rate	Amount
4.	Repair and re-placment laminated both side board of ½” thick in Alluminium panels after removing old damaged board in Girls Hostel entrance lobby 494 sqft. (Board of Duro to be use)	494	Sqft.		
5.	Providing and fixing Al. beading in all panels.	L.S.	L.S		
6.	Repair of Entrance Al. glass door i/e fixing glass pans, locking arrangement complete (L.S.)	L.S.	L.S.		
7.	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:4 (1 cement : 4 coarse sand) for glass bricks -53 cft.	53	Cft.		
8.	Providing and fixing M.S Tubular frame for doors, windows, ventilators etc. complete  170 Kgm.	170	Kgm		
9.	15 mm thick cement plaster in 1:4 (1 cement :4 fine Sand )  24 sqft.	24	Sft.		
10.	Providing and fixing glass bricks with white cement mortar i/e filling gap with white cement i/e snowcem etc. complete  190 Nos.	190	Nos.		
	Total				