

Schedule of Quantities

Name of work : Renovation of Cashier's Room at NSD

S.No.	Items with Specification	Quantity	Rate	Amount
1.	Manufacturing and placing Main table of size 6'-0" x 2'- 3" x 2'-6" with laminated top as per approval and 19mm block board B.W.R. (Century) top and shutter face area laminated with 1mm thick sunmica (Merino) shutters hinges with (hinges and drawer with telescopic channels and S.S. handale and moulding & beadings with melamine palish etc. completed.	1.00		
2.	Manufacturing and placing second table of size 3' - 0" x 1'-6" x 2' -6" Computer with 19mm block board B.W.R. (Century) top and drawer/shutter area laminated with (Merino) 1mm thick sunmica key board slide with telescopic channels and shutter with auto hinghes and all edges 5x20mm Margin C.P. teak wood Moulding and beading melamine polish etc. completed.	1.00		
3.	Cabinets at the wall lavel with board/glass shelves laminated inside and 19mm block board B.W.R. (Century) and 1mm thick sunmica (Margin) Molding & Margin melamine polish natural/walnut etc. completed	1.00		
4.	Change laminate of existing shutter of cabinet with 4mm ply below & change accessories etc. completed.	L.S.		
5.	(a) Main Chair (b) Secondary Chair	1.00 2.00		

6.	Glass doors on the main intervene in wood & glass with and blind in of white colour vista/mac brand for the one door 1+1 with blinds	2.00		
7.	Pinup boards and display board with the fabrics as per approval.	L.S.		
8.	Vitrified Tile of Size 2'-0" x 2' -0"	L.S.		
9.	Misc. /electrical works as per site for lighting and A.C.	L.S.		
10.	Painting & Polishing	L.S.		

Conditions :-

1. The work shall be done as per CPWD specifications.
2. Security Deposit @ 5% shall be deducting from gross amount of bill and shall be released after six months from the date of completion.
3. All the damages done during executions shall be rectified at free of cost.